Division 03 - Concrete (Specification Excerpt)

Section 03 30 00 - Cast-in-Place Concrete

2.1 Footings and foundation walls shall have a minimum compressive strength of 4,000 psi at 28 days.

2.2 Interior slabs on grade shall have a minimum compressive strength of 3,500 psi at 28 days.

2.3 Exterior concrete exposed to freezing shall contain air entrainment of 6 percent, plus or minus 1.5 percent.

Part 1 - Submittals and Warranty

1.4 Submit mix designs and product data for review within 14 days after the Notice to Proceed.

1.5 The Contractor shall provide a warranty period of 2 years on structural concrete, from the date of Substantial Completion.

1.6 Written notice of nonconforming concrete shall be given within 14 days of discovery.