Sheet S-001 - Structural General Notes

1. All concrete shall be 3,000 psi at 28 days unless noted otherwise on the drawings.

2. Reinforcing steel shall be ASTM A615 Grade 60 deformed bars.

3. Concrete work shall conform to Specification Section 03 30 00 Revision C.

Project Schedule Milestones

4. Milestone: Substantial Completion at 210 calendar days after Notice to Proceed.